





PLANNING OF GEOTHERMAL PROJECTS IN KENYA

Paul K. Ngugi

Kenya Electricity Generating Company Ltd. (KenGen)
P.O. Box 785, Naivasha
KENYA
pngugi@kengen.co.ke

ABSTRACT

The project cycle for the geothermal projects as implemented by KenGen comprises four phases and nine steps. The phases are resource exploration, resource assessment, plant construction and operation phases. The exploration phase is further subdivided to three development steps: existing data review, detailed surface exploration and exploration drilling. The resource assessment phase is divided into two steps: appraisal drilling and feasibility study. The construction phase comprise two steps; production drilling and construction of the steam gathering pipe network, power plant and transmission line construction. The work plans developed are used by the execution team as a road map to power plant commissioning which is the ultimate development objective and are also used for soliciting for funds from funding institutions. The planning entails scheduling of the various activities comprising the project activities and how they interrelate. The activities comprise the legal or regulatory requirements, procurement processes that include seeking for KenGen's and funding institution approvals, activities of the funding institutions leading to credit award and the actual site works. The planning aims at optimizing time, cost and procurement of human capacity not resident within KenGen's staff within the legal, regulatory and policy framework existing for each specific project. Project planning computer programs are used particularly Microsoft Project and the key planning outputs are Gantt charts, procurement plans, budgets, cash flow plans and progress reports.

1. INTRODUCTION

1.1 Definitions of work plans

Work plans may be defined as a series of interrelated tasks and activities which when implemented successfully will realize the goals and objectives of a specific project.

1.2 Why project plan

Project planning is an aspect of project management. Project management, a professional discipline, may be defined as "the overall planning, coordination and control of a project from inception to completion aimed at meeting a Client's requirements in order to produce a functionally and financially viable project that will be completed on time within authorized cost and to the required quality standard" (Pearson Education Limited, 1999).

The above definition is more applicable to perspective of the appointed project manager. However, the project plans serve various purposes to various parties involved with the project.

1.2.1 Project owner

Geothermal projects require colossal sums of money to implement. Very few individual institutions and third world governments can implement a sizable geothermal project from internal resource without resulting to soliciting for external funding. Therefore a project plan provides the owner with total project cost, project development period where the project will not make money, cash inflows and outflows and likely profitability. These data is very important for the owner as they approach prospective financiers.

1.2.2 Financiers

Banks are very willing to loan out funds. However, they are averse to adverse risk exposure. They will evaluate a long list of potential risks and in particular administration risks and projected profitability as a basis for servicing of the loan to be advanced. Often times, bilateral and multilateral financial agencies have required engagement of consultants to enhance project management functions. A well packaged project plan assures the banks of a capable project management team. The project plans also provides the banks with an instrument for economic and financial project evaluation. The work plans act as a basis for owner's contractual obligations with the bank and a reference for project progress evaluation and monitoring.

1.2.3 Project execution management team

To the execution team, the work plans are the road map for the project implementation. They capture the projects concepts, requirements, identifies what needs to be done, assigns responsibility to those who will do what needs to be done, defines how it will be done and identifies and assigns the requirements to enable the work to be done. In many times they also identify the authorities and approval to be sought in the process of the project implementation.

The work plans further highlights the milestones that must be achieved and thereby identify the critical aspects of the project. They also act as instruments of communication. In addition, they serve as instruments of performance measurement and control. Regularly the project implementation progress is assessed against the set out milestones in the work plan and where discrepancies occur adjustments are made. On the other hand costs are monitored to ensure that the project has sufficient funding and to address any budget overruns.

1.2.4 Resource persons

They are a reference for level of performance requirement and additional departmental planning.

1.3 Project cycle

A project is time-bound, with definite start and a finish date. A project cycle can be thought as a sequence of logically linked activities in which each is necessary and is a prerequisite for the next stage in the cycle. Project generally grouped into five distinct categories (Figure 1).




FIGURE 1: Project Cycle

1.3.1 Project identification

Identification is the very beginning of the project cycle. At this point the project is defined in very general terms. In many times, at this step, there more questions than answers.

1.3.2 Project formulation and preparation

This stage includes pre-feasibility and feasibility stages. It involves a consideration of all aspects namely; technical, financial, economic, social, cultural, managerial and political aspects. The basic rational of the project is thus examined at this stage especially to identify obvious reasons why the project may not or is unlikely to go on.

1.3.3 Appraisal

Appraisal stage is when detailed project is undertaken especially, where donors are involved, they will involved there technical team, internal staff or consultants, and the resulting plan will be implemented.

1.3.4 Implementation

This entails the execution of the agreed works plan.

1.3.5 Evaluation

Where donors are involved, project evaluation is carried to identify lessons learned. In particular the evaluation will refer back to the project objectives and the work plans and establish whether the objectives were met and if the work plan were appropriate.

The work plans are a result of the work done during project formulation and preparation and the appraisal. It is prudent to note that the works plans provide value to the entire project phases.

1.4 Project parameters

During a projects life, management focuses three basic parameters; quality, cost and time (Figure 2). However, for those working in donor funded and government owned projects must addition factor in the law, policy, rule and




FIGURE 2: Basic Project Elements

regulations which can derail the project if not observed. These parameters must be specified in detail during the planning of the project and are to be adhered to during implementations. These parameters are addressed through specifications, budgets, time schedules and the various policies, rules and regulations applicable to a specific project.

1.5 Key project inputs

Projects use specific inputs (resources) to produce particular outputs over a specified time period in order to meet an identified development need of clearly identified target group. The key project

resources are people, equipment and materials. The work plans identify, plans for, costs and optimizes the use of each of the resources.

1.6 Planning process

The crucial phase involves the breaking down of the various activities and tasks required to complete the project along the three basic parameters while taking to consideration of the law, policy, rules and regulations. The steps involved in planning include:

- Establish the project objectives
- Choose a basic strategy for achievement of the objectives
- Break the project down into subunits of task and activities
- Determine the performance standards for each subunits
- Determine how much time is required to complete each subunit
- Determine the proper sequence for completing the subunits and aggregate this information into a schedule for the total project
- Determine the cost of each subunit and aggregate costs into the project budget
- Determine the staff organization, including the number and kind of position and the duties and responsibilities of each
- Determine what training, if any is required for project team members
- Identify the applicable laws, policy, rules and regulations

2. REVIEW OF THE DEVELOPMENT PHASES

Mwangi (Mwangi, 2007) has reviewed the planning concept used in geothermal project planning in Kenya. The entire geothermal project cycle can be summarized as shown in Figure 3 (Price Water House Coopers. 2007). There are four major phases and nine key steps in the development of geothermal project.




FIGURE 3: Geothermal development phases

PHASE 1: RESOURCE EXPLORATION

Step 1: Review of Existing Data

Objective: The objective is to collate available data gathered overtime by various agencies

involved in studies and research with the aim of identifying gaps on the information

base and strategizing on further works.

Scope of work: This entails a desktop review and analysis of existing data by various disciplines of

earth sciences (geology, geophysics and geochemistry) and engineering (surface

heat measurement).

Duration: The duration for this step may only be a month. Various disciplines would be

involved.

Organization: KenGen has an in-house capacity and carries out this exercise

Output: An inception report would result detailing the information gap and the detailed

program for undertaking surface exploration.

Costs: The cost is negligible

Step 2: Detailed surface exploration

Objective: The objective is to define the resource by its key system characteristic namely:

existence of a heat source in the form of hot magmatic body near earth surface, existence of hydrological system, its characteristics (i.e. flow direction) and

geological structures controlling it and area extent of the prospect.

Scope of works: This entails field measurements, sample collections, laboratory tests, studies and

analysis by various disciplines of earth sciences (geology, geophysics and geochemistry) and engineering (surface heat measurement). In addition, baseline

environmental studies are undertaken.

Organization: KenGen has internal capacity that carries out this step. It also engages consultants

to offer peer review services.

Duration: For most fields, surface works takes about three months.

Out Put: The main output from this step is a conceptual model of the geothermal system and

siting of the discovery (exploration) wells.

Cost: The budget for this step has been within US\$ 0.5 million per prospect.

Step 3: Exploration drilling

Objectives: The main objective is to prove the resource inferred by the geoscientific studies by

drilling a discovery well at the best point according to the conceptual model and

confirm the results with one or two additional wells.

Scope of work: This step marks the beginning of the physical development on any prospect. The

key activities in this step include:

• Main access road and drill pad construction

• Establishment of drilling water and pumping installation. The pumping may be powered by diesel driven generators or electricity where economically accessible.

• Acquisition of land entry rights through negotiation for compensation or purchase

- Other logistical requirements e.g. accommodation, storage, security, offices etc.
- Drilling and testing of three exploration wells.
- Acquisition of environmental license.

Organization: For short distances of access roads, KenGen has internal capacity and undertake the

civil works. For long stretches of access road, KenGen contracts out the earth works. The water installation works are also contracted out except operating and maintenance of the plants, which is done in-house. The drilling works can either be contracted or carried out internally depending on rig availability. The application

for environmental clearance is done in-house.

However, KenGen engages consultants for peer review.

Output: Resource discovery by discharging wells and most importantly a go or no go

decision for further development.

Duration: One year is allowed to undertake the initial logistical requirements. These include

opening the area up by construction of roads, establish water supply system from surface sources or drilling of borehole and the related pipeline , pumping system

and power sources. The time allows acquisition of land access rights and the compensation processes. Drilling requires storage facilities and security systems e.g. fencing, store house or containerized storage. Within the same period, procurement of overseas materials is carried out and contracts for provision of local materials made. The materials may require some advance preparation e.g. slotting. Six months is allowed for the actual drilling.

Cost:

For the advance logistical requirements, a budget figure of US\$ 5.2 million is allowed. The well cost are estimated at US\$ 4.3 million per well using KenGen rigs. However, the actual cost for this step varies from one prospect to another.

PHASE 2: RESOURCE ASSESSMENT

Step 4: Appraisal drilling and well testing

Objective: Appraisal drilling follows a successful drilling exploration program. It is aimed at:

- Sizing the resource in terms of possible output necessary for power plant sizing;
- Determining well productivity characteristics (average fluid output per well and steam fraction) necessary for determining cost of investments and drilling requirements.
- Determining the reservoir fluids characteristics in particular, pressure at the surface (wellhead), dissolved solids that may lead to deposition and dissolved gas content which impact power plant designs and performance.
- Proving a certain fraction of required steam for a plant as a precondition for funding

Scope of work:

The standard practice for KenGen is to drill and test six appraisal wells and may increase this number to nine if necessary.

Output:

All the above data is obtained in preparation of feasibility study. Data and go or no go decision

Organization:

The drilling is carried out in-house if KenGen has an available rig but KenGen may contract a rig but manage the drilling process. KenGen has in recent past contracted drilling consultancy and supervision to beef up its capacity. The additional civil works are carried out in-house. Where earth moving equipment shortages are encountered, these are hired on short contracts.

Duration:

The total duration takes about 15 months. Drilling takes about 12 months while testing of the last well is allowed 3months to heat up and be flow tested.

Costs:

The well costs is estimated at about US\$ 4.3 per well including the civil works. Testing is estimated at US\$ 40,000 per well

Step 5: Feasibility study

Objective: The main objectives of the feasibility studies are:

- Matching existing power plant technologies to resource characteristics and establish a preliminary design
- Carrying out a financial and economic analysis to establish project viability
- Identifying resource management issues that will arise during exploitation and how to mitigate them
- Undertaking environmental impact study scoping

Scope of work:

This is mainly a desktop study. It essentially collates all the data so far accumulated and relates it to the proposed power project. One key aspects taken to consideration

is simulation studies establish sustainable resource exploitation and coming up with

the preliminary design parameters

Output: Bankable feasibility study which KenGen and funding institutions would use for

funding purpose. In addition the feasibility study proposes the appropriate

technology to be used to optimize the resource.

Organization: This step has been contracted to consultants especially because of the comfort of the

lending institutions. However, both KenGen's Board of Consultants and KenGen

staff would review the reports.

Duration: The feasibility study is allowed a six months period.

Costs: This may take up to US 2 million depending on the scope of the project.

PHASE 3: POWER PLANT DEVELOPMENT

Step 6: Production drilling

Objective: At this stage of development, a decision to construct a plant is already made. The

drilling is therefore to provide sufficient steam to run the plant. Additional wells are drilled for reinjection purpose. One reinjection well is required for every 4

production wells.

Scope of works: There would be additional civil works to provide additional access roads and site

construction. Wells would be drilled to provide sufficient steam plus about 10% excess at start-up. The wells would be tested. Procurement activities would

continue in this step.

Organization: All civil works would be carried out in-house. Drilling would be carried out both

in-house and through contracts depending on rigs availability. Well testing would be carried out in-house. A drilling consultancy and supervision may be considered

to offer support to the existing drilling management staff.

Duration: Allows 60 days per well and is subject to the number of wells to be drilled. For

estimation purpose, we assume exploration will be 50% successful, appraisal 75% successful and production wells 90% successful. For 140 MW plant allowing 10% excess steam at start-up we require 25 production wells. The duration will be 4

years using one rig and 2yrs with two rigs.

Costs: The well costs is estimated at about US\$ 4.3 per well including the civil works.

Testing is estimated at US\$ 40, 000 per well.

Step 7: Power plant design, construction and commissioning

Objective: Detailed design, procure and construct the steam gathering system, power plant

substation and transmission lines

Scope of works: Design, procure, construct, commission the plant and undertaking a comprehensive

environmental impact studies.

Organization: KenGen appoints a project team. The project team contracts a consultant to

supervise the construction contractor. KenGen and the consultants tender, shortlist and contract a contractor(s). The contractor designs, procures and install the plants

and its accessories. KenGen would carry out the full EIA.

Duration: It takes about 30 months to construct the power house, manufacture and ship the

turbine and their accessories. The steam field and the transmission lines will be

constructed in parallel.

Cost: The power plant including the power house and all that goes into the power plant

are estimated at US\$ 2.5 million per MW for plants less than 50 MW, US\$2.3 million those between 50 and 100 MW and US1.8 Million for plants size larger than 100 MW. The steam pipeline cost is estimated at US\$ 25 million for a 70 MW

plant and US\$ 37.5 million for a 140 MW plant.

Step 8: Reservoir management

Objectives: Monitoring to ensure steam availability to the plant, monitor pressure drawdown

and scaling problems.

Scope of Work: Entails regular measurement of well productivity, wellhead pressure and chemical

composition of the well effluent. It may involve tracer injection and cold re-

injection activities.

Organization: This is carried out internally.

Duration: Will be carried out for the entire operation period of the plant. **Cost**: Will greatly vary. This is operations and maintenance cost.

Step 9: Operations

Objective: This entails the operations and maintenances of the power plant to ensure

continuous generation.

Scope of works: This will include operation of the plant on a 24hr basis, regular maintenance and

scheduled overhauls over the plant life.

Organization: It is carried out internally. The staff requires to be trained for the plant operations.

Duration: Plant life

Cost: Operation and maintenance cost

3. LAW, RULES AND REGULATIONS

3.1 Geothermal Act, 1982

The act provides:

- For the purpose of exploration, the Minister of Energy authority in writing is required whose life is one year and may be renewable (Part II, Clauses 6).
- Reasonable notice of the intention to enter upon any land shall be given to the owner or occupier of the land.
- One needs to apply for geothermal license for the purpose of exploitation. The application to be accompanied by a fee. The life of the license is not greater than 30 years (Part II, Clause 7).
- The land owners shall be compensated for the losses incurred pursuant to geothermal development (Part IV, Clauses 18-23).

3.2 Environmental management and co-ordination act, 1999

The act provides:

- No project will commence without submission of a project report.
- The National Environmental Management Authority (NEMA) will evaluate the report and if in their opinion it will have major impact, the project owner will be required to carry out an environmental impact assessment study (EIA).
- The report is submitted back to NEMA with a fee.
- The Authority shall respond to the application within three months without which the applicant may proceed.
- Upon receipt of the EIA document, NEMA shall cause a notice to be published in the official government news print, the Kenya Gazette including a local newspaper.
- Nema will allow the public sixty days perusing and objecting to the proposed project. This period may be extended if an individual applies for extension.

• Only when the public and the Authority is satisfied, will the Authority issue an EIA licences

3.3 The public procurement and disposal act, 2005

(LEGAL NOTICE No. 174, Kenya Gazette Supplement No. 92, 29th December, 2006, Legislative Supplement No. 53)

This Act applies to any body in which the Government has a controlling interest. In summary the act requires that:

- All international tendering will be allowed 30 days to prepare tender. If one was to use prequalifications one has to allow at least 14 days to prepare the prequalification documents. This require advertisement in the local and where possible international journal etc.
- National tendering requires bidders to be allowed at least 21 days to prepare their bid. In addition if the projected cost is estimated over Kshs 6 million (US 0.75 million) for goods and works and US\$ 0.375 million for services will require to be advertised in the local newspapers.
- The tender documents are evaluated by a committee and approved by an official tender committee.
- The contract cannot be signed before 14 days after award to allow for complaints and appeal to the award.

3.4 Funding institution rules and regulations

3.4.1 Funding cycle

Receiving funding from donors follow a process that take about a year and may last longer. The process begins with project identification, formulation and appraisal. The funding for the project would then be presented for approval. The approving board meets once every about 4 to 6 months. After the approval, it still takes time to carry out financial negotiation

3.4.2 Procurement regulations

Prior to publication or invitation to pre-qualify or tender, the following documents are often time submitted to the funding institution for a approval without which the process may not be funded under the credit. These are:

- Invitation to tender
- Selection criteria for qualification (in detailed form)
- Tender documents, including specimen contract
- Draft notice specifying the fees for the purchase of the tender documents and their utilization, as well as list of the media in which the notice is to be published

In processes with pre-qualification, the following documents have to be submitted to the funding institution for comment prior to the invitation to tender:

- The evaluation report of the qualification, including the certificate or opinion of the consultant
- The recommendation on the list of bidders to be invited to tender

In processes with post-qualification, the following documents have to be submitted to funding institution for comment prior to the opening of the bids:

• The evaluation report of the qualification, including the certificate or opinion of the consultant

• The recommendation on the list of bidders whose financial bids are to be opened.

Prior to the award of the contract, the following documents are to submitted the funding institution for comment:

- The signed record of the bid opening
- The evaluation report
- The recommendation on the award
- The certificate or opinion of the consultant on the recommendation of the award
- If applicable, an explanation why the binding period could not be observed
- At the request of funding institution, if applicable, all or specific bids.

In addition the funding institutions require that the bidders be allowed at least 30 days to prepare prequalification bids and at least about 45 days to prepare actual bids.

3.5 The water act

The water act provides that authority is required for abstraction of water whether from surface bodies or underground. Geothermal projects require water for the drilling process and also the mining of the geothermal fluids falls within this categorization. This process requires an application to be made. A regional board would then consider the application and grant approval. This can take over six months.

4. SCHEDULING

As stated above a project has a specific start and finish date. The above information is generic and needs to be customized for a specific project. This activity is called scheduling. The steps involved in scheduling are:

- Enter the project phases, milestones and tasks into table on a paper, white board, a spreadsheet, or word processor. You may also enter the data into a Gantt chart or network diagram
- The next aspects is to calculate dates, start and finish for each activity and enter them in the table
- Link tasks with their appropriate relationships to one another. Note that some tasks cannot begin until certain previous undertaken task has been completed. Again certain tasks compete for resources hence a certain task may not begin until a limited resource is available.
- Review the program so as to take care of any deadlines and other date constraints
- Assign resources to the various tasks and optimize the resources so as not to over allocate resource thereby creating conflict or under allocate resources which leads to higher project costs
- Establish the budget for the project;
- It is increasing becoming a requirement to have a separate procurement plan. Hence one would extract the aspects of procurement from the main plan.

For a simple project, working with a paper or white board may be adequate. However, geothermal projects take many years and have very many interrelated tasks. In addition, optimization of the project plan requires working forward and backwards and can be very taxing. Several computer programs exist that aid the planners in the optimization of the work plans. The programs in particular aid the planners to:

- Calculate the start and finish dates
- Indicate whether assigned resources are actually available

- Inform you if the assigned resources are under allocated or overworked
- Alert you if you have an upcoming deadline
- Calculated the budget for you once the cost have been included in the program
- Help you to manage and control the project by highlighting activities that have not started after their start date and those that are delayed
- The programs enable the planners to get customized reports in different views e.g. Gantt, network diagram and table

Examples of the project planning computer programs are:

- Microsoft project
- Primavera
- Smart Draw

There are many others that could be found in the internet. In KenGen, Microsoft Project Software is widely use and in limited cases Primavera. The key outputs of interest to KenGen have been Gantt charts, procurement plans, budgets, cash flow plan and progress reports. A typical plan is shown in the appendix.

REFERENCES


Mwangi, M.N. (2007). Planning Of Geothermal Projects: A Case Study on Kenya, Papers and Presentation s at "Short Course III on Surface Exploration for Geothermal Resources" Organized by UNU-GTP and KenGen in Naivasha Kenya, November 2007

Pearson Education Limited, 1999. *Code of Practice for Project Management for Construction and Development*, Second Edition, Edingurgh Gate, Harlow, England, 217pp

PriceWater House Coopers (2007). Establishment of a Geothermal Development Company, Draft master and Business Plan, Nairobi, Kenya, July 2007.

Ngugi 12 Planning, Kenya

APPENDIX



Planning, Kenya 13 Ngugi

_	Tack Name	Duration	Chart	H Single	Prodocecci	3000
,			00000	9		D N O S V I N I N I N I N I D I D
<u>.</u>	Evaluation	p i	60/97/6	60/1/01	9225F	•
25	Approval	pç	10/1/09		53SF	*
23	Aw ard & Appeal Period	14 d	10/6/09		8	
72	Delivery	180 d	10/20/09		53	
22	BA License acquisition	167 d?	1/1/10	6/17/10		
26	Prepartion of Project Report	15 d	1/1/10	1/16/10	57SF	
22	Submission of Project report	1 d?	1/16/10	1/17/10 58SF	58SF	
28	Review By NEMA	90 P	1/17/10	2/16/10 59SF	59SF	
29	Undertake BA	45 d	2/16/10	4/2/10	60SF	
09	Submit	1 d?	4/2/10	4/3/10	61SF	
61	Advertise	14 d	4/3/10	4/17/10	62SF	
62	Public Review	P 09	4/17/10	6/16/10 63SF	63SF	
63	Obtain Licence	1 d?	6/16/10		83SF	
2	Acquisition of Land Rights	225 d	11/4/09	6/17/10		
92	Identification of Owners	15 d	11/4/09	11/19/09	45	
99	Approaching the Owners	15 d	11/19/09	12/4/09 65	9	
29	Engage Ow ners into negotiations	P 06	12/4/09	3/4/10 66	99	
89	Apply for approval	P 0E	3/4/10	4/3/10 67		
69	Enter into agreements	45 d	4/3/10	5/18/10 68	89	
20	Pay Compensations	90 g	5/18/10	6/17/10 69	69	
7.1	Water Abstraction License	125 d	11/4/09	3/9/10		
72	Compile Application	2d	11/4/09	11/9/09 45	45	
73	Review by WaterManagement Board	P 06	11/9/09	2/7/10	72	
i			077			
44	Obtain License	30 d	2/7/10	\rightarrow	73	
75	Contract Earth Works	297 d	12/22/09			
9/	Prepare tender	30 d	12/22/09		77SF	
4	Advertise	p 2	1/21/10	1/28/10	78SF	
28	Tender Period	90 g	1/28/10	2/27/10	79SF	
79	Evaluation	2 d	2/27/10	3/4/10	80SF	
80	Approval	2d	3/4/10	3/9/10 81SF	81SF	
81	Aw ard & Appeal Period	14 d	3/9/10	3/23/10 74	74	
82	Mobilization	21 d	3/23/10	4/13/10 81	181	
83	Road and Site Costruction	P 06	6/17/10		82,70	
\$	Construct storage facilities and temporary offices	P 06	2/11/10	10/15/10	83SS+30 d	
82	Establish Water Supply System	5b 689	11/10/08	9/30/10		
98	Survey Sources of Water	15 d	11/10/08	11/25/08		
87	Water Abstraction License	125 d	11/25/08	3/30/09		
88	Compile Application	P9	11/25/08		98	
68	Review by WaterManagement Board	P 06	11/30/08	2/28/09	88	
06	Obtain License	9 OE	2/28/09	3/30/09 89	68	
91	Drilling Of Water Bore holes	293 d?	6/16/09	4/5/10		
92	Prepare tender	90 P	6/16/09	2/16/09	93SF	· · · · · · · · · · · · · · · · · · ·
93	Advertise	p.2	2/16/09		94SF	
76	Tender Period	9 OE	7/23/09	8/22/09	95SF	
92	Evaluation	P9	8/22/09	8/27/09	96SF	-
96	Approval	P9	8/27/09	60/1/06	97SF	=
26	Aw ard & Appeal Period	14 d	9/1/09	9/15/09 98SF	98SF	
86	Mobilization	21 d	9/12/09	10/6/09	99SF	
66	Actual Drilling	p 06	10/6/09	1/4/10	8'06	
100	Water Works Construction	p 06	1/4/10	4/4/10 99	66	

Ngugi 14 Planning, Kenya

102	Commissioning	1 4?	4/4/10	4/5/10	100	N D J F M A M J J J A S O N D J F M A M J J J A
102	,	_		4/4/10		
103	Apply For Bectricity Supply to Boreholes	100 d?	12/25/09			
Ī	Compile Application	1 d?	12/25/09	12/26/09	104SF	¥
4	Assessment	P 06	12/26/09	1/25/10	105SF	
105	Quotation	p 2	1/25/10	2/1/10	107SF	
106	Payment	17 d	2/1/10	2/18/10		
107	Repare Request for Approval	2 d	2/1/10	2/6/10	108SF	
308	Approval	pg	2/6/10	2/11/10	109SF	
100	payment	p 2	2/11/10	2/18/10	110SF	
110	Design & Costruction	45 d	2/18/10	4/4/10	101SF	
111	Laying Of Water Line	45 d	8/16/10	9/30/10	9/30/10 83SS+60 d	
112	Slotting of Liners	202 d	1/31/10	8/21/10		P
113	Repare tender	9 OE	1/31/10	3/2/10 114SF	114SF	
114	Advertise	P 2	3/2/10	3/9/10	115SF	
115	Tender Period	90 P	3/9/10	4/8/10	116SF	
116	Evaluation	2 d	4/8/10	4/13/10	117SF	
117	Approval	2 d	4/13/10	4/18/10	118SF	
118	Award & Appeal Period	14 d	4/18/10	5/2/10 54	22	
119	Mobilization	21 d	5/2/10	5/23/10	118	
120	Actual Works	P 06	5/23/10	8/21/10	119	
121	Contract for Bulk Cement & Diesel Fuel	91 d	7/1/10	9/30/10		
122	Prepare tender	90 g	7/1/10	7/31/10	123SF	1
123	Advertise	7 0	7/31/10	8/7/10	124SF	
124	Tander Period	300	8/7/10	9/6/10		
125	notion level	3 0	0/6/10	0/11/10		
126	Amroval	2 0	9/11/10	9/16/10		
2 2	Application of American	7 00	9/11/10	9/10/10		
/71	Award & Appeal Period	14 d	0L/9L/6	9/30/10	138SF	
87.	Contract Cementing Services	166 d	4/17/10	9/30/10	L	
129	Hepare tender	90 g	4/1//10	01//1/9	130SF	
130	Advertise	7 d	5/17/10	5/24/10		▼
131	Tender Period	45 d	5/24/10	7/8/10		
132	Evaluation	2 d	7/8/10	7/13/10		■
133	Approval	2 d	7/13/10	7/18/10		
134	Award & Appeal Period	14 d	7/18/10	8/1/10	135SF	
135	Mobilization	P 09	8/1/10	9/30/10	138SF	
136	Drilling	310 d	9/30/10	8/6/11		3
137	Well 1	P 06	9/30/10	12/29/10		
138	Rig Mobilization	9 OE	9/30/10	10/30/10	120,111,83,	
139	Actual Drilling	p 09	10/30/10	12/29/10	138	
140	Well 2	p 99	12/29/10	3/4/11		
141	Rig Mobilization	2d	12/29/10	1/3/11	139	
142	Actual Drilling	p 09	1/3/11	3/4/11	141	
143	Well 3	p 99	3/4/11	5/8/11		
44	Rig Mobilization	2 g	3/4/11	3/9/11	142	
145	Actual Drilling	p 09	3/9/11	5/8/11	144	
146	Testing	280 d	10/30/10	8/6/11		
147	Well 1	150 d	10/30/10	3/29/11		
148	Geology	p 09	10/30/10	12/29/10	139SS	
149	Geochemistry	120 d	10/30/10	2/27/11	139SS, 151F	
150	Heat up	9 OE	12/29/10	1/28/11	139	

Planning, Kenya 15 Ngugi

						7.	4
151	Flow testing	30 d	1/28/11	2/27/11			
152	Reports	90 g	2/27/11	3/29/11	151		
153	Well 2	150 d	1/3/11	6/2/11			
154	Geology	p 09	1/3/11	3/4/11	142SS		
155	Geochemistry	120 d	1/3/11	5/3/11	142SS		
156	Heat up	90 P	3/4/11	4/3/11	142		
157	Flow testing	90 g	4/3/11	5/3/11	156		
158	Reports	90 P	5/3/11	6/2/11	157		
159	Well 3	150 d	3/9/11	8/6/11		P	
160	Geology	p 09	3/9/11	5/8/11	145SS	•	
161	Geochemistry	120 d	3/9/11	11/1/11	145SS		
162	Heat up	30 d	5/8/11	6/7/11	145		
163	How testing	90 q	6/7/11	11/1/11	162		
164	Reports	90 g	11/1/11	8/6/11	163		
165	Environment Management	1 d?	7/6/11	11/1/1	N77/11 83SS,163开	L	
166	In-house Reviews	53 d?	7/22/11	9/13/11			
167	Collation of data and reports	30 d	7/22/11	8/21/11	164SS+15 d	•	
168	Review initial Conceptual Model	15 d	8/21/11	9/5/11	167		
169	Presentation	1 d?	9/5/11	9/6/11	168	}	
170	Modification	77	9/6/11	9/13/11	0.5		
74.7	Modification 1	7	1 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	41740			
- (-	DC Neview	3 ·	11/61/6	11/1/01			
172	Posting of reports	30 d	9/13/11	10/13/11	170		
173	Actual meetings	4 d	10/13/11	10/17/11	172		
	Go or No Go	P 0	10/17/11	10/17/11	173	10/17	
	RESOURCE ASSESSMENT	1104 d	12/22/10	12/30/13			
176	Appraisal Program	946 d	12/22/10	7/25/13			
177	Rig Hre	445 d	12/22/10	3/11/12			
178	Pre-Qualification	p 86	12/22/10	3/30/11			
179	Prepation of Expression of Interest	2 q	12/22/10	12/27/10	180SF		
180	Obtain Banks No objection	P 2	12/27/10	1/3/11	181SF		
181	Advertise (local media and international)	21 d	1/3/11	1/24/11	182SF		
182	Bidding Period	90 g	1/24/11	2/23/11	183F		
183	Evaluation & Shortlist Report Preparation	p 2	2/23/11	3/2/11	184SF		
184	KenGen's Approval	p 2	3/2/11	3/9/11	185SF		
185	Obtain Banks No objection	21 d	3/9/11	3/30/11	187SF		
186	Tendering	347 d	3/30/11	3/11/12		-	Ì
187	Preparation of bidding Documents	90 g	3/30/11	4/29/11	188F		•
188	Obtain Banks' no objection	21 d	4/29/11	5/20/11	189SF		
189	Issue bid documents + tendering	45 d	5/20/11	7/4/11	191SF		
190	Technical Evaluation	35 d	7/4/11	8/8/11			
191	Evaluation	p 2	7/4/11	7/11/11	192SF		
192	KenGen Approval	p 2	7/11/11	7/18/11	193SF		
193	Obtain Bank's no objection	21 d	7/18/11	8/8/11	195SF		
194	Commercial Evaluation	p 02	8/8/11	10/17/11			
195	hvite bidders for tender openining	21 d	8/8/11	8/29/11	196SF	•	
196	Evaluation	p 2	8/29/11	9/5/11	197SF		
197	KenGen Approval & Appeal	21 d	9/5/11	9/26/11	198SF		
198	Obtain Bank's no objection	21 d	9/26/11	10/17/11	200SF	<u></u>	
199	Contract Negotaition	26 d	10/17/11	12/12/11			
200	Invite bidders for Negotiation	21 d	10/17/11	11/7/11	174		

Ngugi 16 Planning, Kenya

Task Name		Duration	Start	Finish	Predecessor F M A M
	Rig Mobilization	2 d	5/11/12	5/16/12	249
	Actual Drilling	P 09	5/16/12	7/15/12 251	:51
	Well 6	p 99	7/15/12	9/18/12	
	Rig Mobilization	5 d	7/15/12	7/20/12	252
	Actual Drilling	p 09	7/20/12	9/18/12 254	554
	Testing First Three wells	280 d	3/12/12	12/17/12	
	We II 4	150 d	3/12/12	8/9/12	
	Geology	p 09	3/12/12	5/11/12	249SS
۱ ۱	Geochemistry	120 d	3/12/12	7/10/12	249SS
۱	Heat up	30 d	5/11/12	6/10/12 249	449
	Flow testing	30 d	6/10/12	7/10/12 260	093
- 1	Reports	30 d	7/10/12	8/9/12 261	191
- 1	Well5	155 d	5/11/12	10/13/12	
	Ceology	90 0	5/11/12	71.01.17	2000
	Geochemstry	120 d	5/16/12	9/13/12 25255	SS2S
	Heat up	30 d	7/15/12	8/14/12 252	552
- 1	Flow testing	30 d	8/14/12	9/13/12	266
	Reports	p 06	9/13/12	10/13/12	267
	We II 6	120 d	7/20/12	12/17/12	
1	Geology	p 09	7/20/12	9/18/12 255SS	:55SS
	Geochemistry	120 d	7/20/12	11/17/12 255SS	:55SS
1	Heat up	90 P	9/18/12	10/18/12 255	.55
	Flow testing	90 g	10/18/12	11/17/12	272
	Reports	90 g	11/17/12	12/17/12	273
	Exploration Strategy review	31 d	12/17/12	1/17/13	
	Data Collation	90 g	12/17/12	1/16/13 274	774
i .	Presentation and Review	1 d	1/16/13	1/17/13 276	32
	Drilling of Remaining Three wells	310 d	9/18/12	7/25/13	
	oring First	D 027	3/10/12	61.07/4	
- 1	Well 7	P 06	9/18/12	12/17/12	11
	r4g Mobilization	30 d	9/18/12	10/18/12 255	(55
	Actual Drilling	p 09	10/18/12	12/17/12 281	181
	We II 8	9 d	12/17/12	2/20/13	
	Rig Mobilization	2 d	12/17/12	12/22/12 282	.82
ĺ	Actual Drilling	p 09	12/22/12	2/20/13 284	.84
	Well 9	9 de	2/20/13	4/26/13	
	Rig Mobilization	2 d	2/20/13	2/25/13 285	.85
	Actual Drilling	p 09	2/25/13	4/26/13	287
1	Testing Remaining Three wells	280 d	10/18/12	7/25/13	
1	Well 7	150 d	10/18/12	3/17/13	
ĺ	Geology	p 09	10/18/12	12/17/12 282SS	.82SS
1 1	Geochemistry	120 d	10/18/12	2/15/13 282SS	85288
('	Heat up	90 d	12/17/12	1/16/13	282
	Flow testing	p 06	1/16/13	2/15/13	293
	Reports	90 Q	2/15/13	3/17/13 294	94
	We II 8	150 d	12/22/12	5/21/13	
	Geology	p 09	12/22/12	2/20/13 285SS	:85SS
- 1	Geochemistry	120 d	12/22/12	4/21/13 285SS	855S
- 1	Heat up	30 9	2/20/13	3/22/13	285
300	How testing	90 g	3/22/13	4/21/13 299	66:

Planning, Kenya 17 Ngugi

Duration Start Frish	2013 2014 3 0 N D J F M A M J J A S 0 N D J		•								· · ·																				F					11/29				1230				•		
Peports Duration State	Predecesson M A	5/21/13 300	7/25/13	4/26/13 288SS	6/25/13 288SS	5/26/13 288	6/25/13 305	7/25/13 306	12/30/13	5/3/13	5/18/12 312SF	5/25/12 313SF	6/15/12 314SF	7/15/12 315SF	7/22/12 316SF	7/29/12 317SF	6/18/12 3193F	9/18/12 320SF	10/9/12 321SF	11/23/12 323SF	12/28/12	11/30/12 324SF	12/7/12 325SF	12/28/12 327SF	3/8/13	1/18/13 328SF	PSS2S (1/27/1	3/8/13 332SF	5/3/13	3/29/13 333SF	4/5/13 334SF	4/26/13 335SF	5/3/13 288	11/29/13	11/20/13 337	11/29/13 338	12/30/13	12/29/13 339	12/30/13 341	12/30/13 342	6/8/18	1/29/14	4/4/13 347SF	7/3/13 348SF	10/1/13 349SF	12/30/13 350SF
Reports Geology Geology Geochernistry Heat up Heat up Reports Reports Reports Reports Reports Reports Reports Barks No objection Into & Shortlist Report Preparation Into Approval Barks No objection Into Evaluation Into Evaluation Into Evaluation Into Contracts Into Preparation Into Objection Into Preparation Into Objection Into	Start	4/21/13	2/25/13	2/25/13	2/25/13	4/26/13	5/26/13	6/25/13	5/13/12	5/13/12	5/13/12	5/18/12	5/25/12	6/15/12	7/15/12	7/22/12	8/19/12	8/19/12	9/18/12	10/9/12	11/23/12	11/23/12	11/30/12	12/7/12	12/28/12	12/28/12	1/01/13	1/25/13	3/8/13	3/8/13	3/29/13	4/5/13	4/26/13	5/3/13	5/5/13	11/29/13	11/29/13	11/29/13	12/29/13	12/30/13	3/5/13	3/5/13	3/5/13	4/4/13	7/3/13	10/1/13
Peports Well 9 Geology Geology Geology Hare of Cons ultents Per-dualification Pepation of Expression of Interest Obtain Barks No objection Advertise (Local media and international) Bidding Period Evaluation & Shortlist Report Preparation Advertise (Local media and international) Bidding Period Evaluation & Shortlist Report Preparation Advertise (Local media and international) Bidding Period Evaluation & Shortlist Report Preparation KenGen's Approval Obtain Barks no objection Evaluation Evaluation KenGen's Approval Obtain Barks no objection Evaluation KenGen Approval & Appreal Obtain Barks no objection Invite bidders for tender openining Evaluation KenGen Approval & Appeal Obtain Barks no objection Signing of contract Negotation Negotiation Negotiation Negotiation Negotiation Negotiation Resemitation and Review Go or No Go NNSTRUCTION HASE Funding Application Replect Formulation and Preparation Repression of Barkation Replect Hemitication Replect Formulation and Preparation Appraisal	Duration	30 d	150 d	p 09	120 d	30 d	p 06	90 g	D 96G	355 d	5 0	D 0 2	21 d	30 d	D 2	p 2	257.0	30 d	21 d	45 d	35 d	D 2	p 2	21 d	D 07	21 d	2 - 2	21 d 21 d	5.5 5.6 9.6	21 d	p 2	21 d	2 d	210d	30 d	PO	31 d	9 OE	1 d	P 0	1921 d	330 d	90 g	p 06	p 06	p 06
		Reports	Well 9	Geology	Geochemistry	Heat up	Flow testing		ystudy	or consultants	Prenation of Expression of Interest	Obtain Banks No objection	Advertise (local media and international)	Bidding Period	Evaluation & Shortlist Report Preparation	KenGen's Approval	Cotain Banks NO objection	Peparation of bidding Documents	Obtain Banks' no objection	Issue bid documents + tendering	Te chnical Evaluation	Evaluation	KenGen Approval	Obtain Bank's no objection	Commercial Evaluation	Invite bidders for tender openining	Evaluation	KenGen Approval & Appeal Obtain BanKs no objection	Contract Negotaition	Invite bidders for Negotiation	Negotiation & Drafting of contract	Obtain Banks no objection	Signing of contracts	ntract Performance	Auvance rayment	Submission of Bankable report	C Review Meeting	Data Collation	Presentation and Review	Go or No Go	ON PHASE	Application	ect Identification	ct Formulation and Preparation	aisal	Funding institution Approval

Ngugi 18 Planning, Kenya

Contract Finement 190 19	<u>.</u>	Task Name	Duration	Start	Finish	Predecessor S O N	2014 2015 2015 2015 2015 2015 2015 2015 2015
Production Drilling 746 d 926213 6101016 Oversea Procurement 271 d 11/13/13 874144 Oversea Procurement 30 d 11/13/13 12/20/13 Arbertes 7 d 12/20/13 12/20/13 Arbertes 30 d 12/20/13 12/20/13 Arbertes 30 d 12/20/13 11/20/13 Approval 5 d 11/20/14 12/20/13 Approval 10 d 12/20/13 11/20/14 Approval 10 d 12/20/14 11/20/14 Approval 10 d 11/20/14 11/20/14 Award & Appeal Period 11 d 11/20/14 11/20/14 Award & Appea	351	Credit Efectiveness	PO	1/29/14		-	1/29
Oversaase Procurement 271 (11/31) 11/13/13 8 11/14 Pageane Ended 70 (20/31) 1/20/31 1	352	Production Drilling	745 d	9/25/13	10/10/15		
Peperce tendor	353	Overseas Procurement	271 d	11/13/13	8/11/14		
Abvertise 7 d 71/21/31 120/20/3 Funder Percic 30 d 1726/13 11/29/14 11/29/14 11/29/14 Funder Percic 50 d 11/29/14 11/29/14 11/29/14 11/29/14 Award & Appeal Period 14 d 11/29/14 11/29/14 11/29/14 11/29/14 Pepare Enrick 7 d 50/24 11/29/14 11/29/14 11/29/14 Award & Appeal Period 30 d 30/24/1 11/29/14 11/29/14 Avertise 10 d 30 d 30/24/1 30/24/1 30/24/1 Avertise 10 d 30 d 30/24/1 10/24/1 10/24/1 Avertise 10 d 30 d 30/24/1 10/24/1 10/24/1 Avertise 10 d 30 d <th>354</th> <th>Prepare tender</th> <th>90 g</th> <th>11/13/13</th> <th></th> <th>35SF</th> <th></th>	354	Prepare tender	90 g	11/13/13		35SF	
Fender Pended 70 72,019 11,1914 11,1	355	Advertise	p 2	12/13/13		36SF	
Pediation	356	Tender Period	90 g	12/20/13	1/19/14	7SF	
Approval 5 d 1729/14 1029/14 Delivery 14 d 1729/14 21/29/14 Delivery 30 d 5/26/14 21/21/14 Pepare tender 30 d 5/26/14 1/24/14 Advertee 7 d 6/26/14 1/24/14 Inneh Pepare tender 30 d 5/26/14 1/24/14 Advertee 7 d 6/26/14 3/2/14 Approval 80 d 8/2/14 3/2/14 Award & Appeal Percot 30 d 8/2/14 3/2/14 Approval 7 d 10/14/14 1/2/14/14 Perpate ender 30 d 1/1/14 1/2/14/14 Advertee 10 d 1/2/14 1/2/2/14 Advertee 10 d 1/2/2/14 1/2/2/14 Advertee 10 d 1/2/2/2 1/2/2/2	357	Evaluation	2 d	1/19/14	1/24/14	38SF	<u> </u>
Avaid & Appeal Period 14 d 112974 2072/14 2072/14 2072/14 2071/14 2071/14 2071/14 2071/14 2071/14 2071/14 2071/14 2071/14 2071/14 2072/14	358	Approval	2 d	1/24/14	1/29/14	39SF	
Stocking of Linears 180 21214 Sifty	359	Award & Appeal Period	14 d	1/29/14	2/12/14	150	
Souting of Liners 202 d 5582H4 b 5014H4 Prepare tender 30 d 552H4 b 505H4 b Advertise 7 d 675H4 b 505H4 b Advertise 30 d 772H4 b 707H4 b Prepare tender 30 d 772H4 b 80FH4 b Award & Appeal Period 30 d 772H4 b 80FH4 b Award & Appeal Period 30 d 772H4 b 80FH4 b Award & Appeal Period 30 d 91FH4 b 80FH4 b Actual Works 30 d 91FH4 b 91FH4 b Pepare tender 30 d 91FH4 b 91FH4 b Advertise 30 d 91FH4 b 97FH4 b Advertise 30 d 91FH4 b 10FH1 b Advertise 30 d 91FH4 b 10FH1 b Advertise 30 d 10FH4 b 10FH1 b Advertise 30 d 10FH4 b 10FH4 b Advertise 30 d 10FH4 b 10FH4 b Advertise 30 d 10FH4 b	360	Delivery	180 d	2/12/14		65	
Pepare tender	361	Slotting of Liners	202 d	5/26/14	12/14/14		
Advertise 70 6725/4 7/2/14 Inchiper Period 50 7/2/14 7/2/14 Evaluation 50 7/2/14 8/1/14 Approval 60 8/1/14 8/1/14 Approval 140 8/1/14 8/1/14 Actual Works 90 9/1/2/14 8/1/2/14 Actual Works 90 9/1/2/14 10/2/14 Actual Works 10 1/2/2/14 10/2/14 Actual Works 10 1/2/2/14 10/2/14 Actual Morents 10 1/2/2/14 10/2/14 Actual Morents 10 1/2/2/2 1/2/2/2 Actual Morents 10 1/2/2/2 1/2/2/2 Actual Morents 10 1/2/2/2 1/2/2/2 <	362	Prepare tender	90 g	5/26/14	6/25/14	33SF	
Tender Perool	363	Advertise	p 2	6/25/14	7/2/14	4SF	
Preparetion	364	Tender Period	90 g	7/2/14	8/1/14	35SF	
Approval 5 d 86/14 8/11/14 Award & Appeal Period 11 d 8/11/14 8/11/14 Award & Appeal Period 20 d 9/15/14 9/15/14 Abolization 30 d 9/15/14 12/14/14 Abornated Ferbed 30 d 9/15/14 12/14/14 Abornated Ferbed 30 d 9/14/14 10/14/14 Abornoval 5 d 1/12/14 10/14/14 Abornoval Approval 5 d 1/12/14 10/14/14 Abornoval Approval 5 d 1/12/14 10/14/14 Abornoval Approval 5 d 1/12/14 10/14/14 Abornoval Abornoval 1 d 1/12/14 10/14/14 Abornoval Abornoval 1 d 1/14/14 10/14/14 Abornoval 1 d 1/14/14 10/14/14<	365	Evaluation	2 g	8/1/14	8/6/14	36SF	
Mobilization	366	Approval	5 d	8/6/14	8/11/14	37SF	
Mobilization	367	Award & Appeal Period	14 d	8/11/14		00	
Actual Works 90 g 91514 p 121414 Contract for Bulk Cement & Diesel Fuel 91 d 91414 p 121414 (101414 p Pepae Lender 30 d 91414 p 101414	368	Mobilization	21 d	8/25/14	9/15/14	25	
Contract for Bulk Cement & Desei Fuel 914 1214414 1214414 1214414 1014414 1014414 1014414 1014414 1014414 1014414 1014414 1014414 1014414 1014414 1014414 1014141 1014414 1014141 1014414 1014141 1014414 10141414 1014141 1014141 1014141	369	Actual Works	P 06	9/15/14		88	
Advertise	370	Contract for Bulk Cement & Diesel Fuel	91 d	9/14/14	12/14/14		
Tender Perod	371	Prepare tender	90 g	9/14/14		72SF	
Frider Period	372	Advertise	p 2	10/14/14	10/21/14	73SF	
Evaluation 5 d 11/26/14 11/25/14 Award & Approval 5 d 11/25/14 11/30/14 Contract Cementing Services 166 d 7/11/14 11/30/14 Fepare tender 30 d 7/11/14 12/14/14 Advertise 7 d 7/31/14 8/71/14 Fepare tender 7 d 7/31/14 8/71/14 Advertise 7 d 7/31/14 8/71/14 Evaluation 5 d 9/21/14 8/71/14 Abproval Approval 10 d 10/11/14 10/11/14 Award & Appeal Period 10 d 10/11/14 10/11/14 10/11/14 Award & Approval 6 d 9/26/14 10/11/14 10/11/14 Award & Approval 7 d 9/26/14 10/11/14 10/11/14 Award & Approval 7 d 9/26/14 10/11/14 10/11/14 Advertise (local media and international) 2 d 9/26/14 10/11/14 Advertise (local media and international 2 d 10/21/14 10/21/14	373	Tender Period	90 g	10/21/14		74SF	
Approval 5 d 11/25/14 11/30/14 11/30/14 11/30/14 12/14/14 Contract Cennenting Services 166 d 7/1/14 12/14/14	374	Evaluation	2q	11/20/14		75SF	
Award & Appeal Period 14 d 113014 121414 Contract Cementing Services 166 d 7/1/14 12/14/14 Pepare tender 30 d 7/1/14 12/14/14 Advertise 7 d 7/1/14 7/1/14 7/1/14 Evaluation 6 d 9/2/1/14 9/2/1/14 9/2/1/14 Approval Award & Appeal Period 1/4 d 10/1/14 10/1/14 Hre of Second Rig 45 d 9/2/1/14 10/1/14 Award & Approval 60 d 10/1/14 10/1/14 Preparation of Expression of Interest 5 d 9/2/1/14 10/1/14 Award & Awards wo objection 7 d 10/2/1/1 10/2/1/1 Advertise (local media and International) 2 d 10/2/1/1 10/2/1/1 Advertise (local media and International) 2 d 10/2/1/1 10/2/1/1 Advertise (local media and International) 2 d 10/2/1/1 10/2/1/1 Advertise (local media and International Explanation 7 d 11/2/1/1 10/2/1/1 Approval 7 d <	375	Approval	5 d	11/25/14	11/30/14	76SF	
Contract Cementing Services 166 d 7/1/14 b 12/14/14 c Repare tender 30 d 7/1/14 c 7/3/1/14 c 8/3/1/14 c 8/3/1/14 c 8/3/1/14 c 9/3/1/14 c 10/1/14 c	376	Award & Appeal Period	14 d	11/30/14	12/14/14	IGSF	
Advertise	377	Contract Cementing Services	166 d	7/1/14	12/14/14		
Advertise 7 d 7/31/14 8/7/14 Tender Period 45 d 8/7/14 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 9/2/1/4 1/2/1	378	Prepare tender	90 g	7/1/14	7/31/14	79SF	
Tender Period	379	Advertise	p 2	7/31/14	8/7/14	30SF	
Evaluation 5 d 922/14 926/14 Award & Approval 5 d 926/14 10/1/14 Award & Appeal Period 14 d 10/1/14 10/1/14 Mobilization 60 d 10/1/14 10/1/14 Hre of Second Right 445 d 926/13 12/14/14 Pre-Qualification 36 d 926/13 1/11/14 Prepatent of Expression of Interest 5 d 926/13 1/11/14 Obtain Banks No objection 7 d 930/13 1/11/14 Advertise (local media and international) 21 d 10/7/13 10/2/13 Evaluation & Shortist Report Preparation 7 d 11/2/13 11/2/13 Kendeans Approval 7 d 11/2/13 12/11/13 Kendeans Approval 7 d 11/2/14 12/11/13 Mobian Banks No objection 21 d 12/11/14 12/11/14 Preparation of bidding Documents 21 d 12/11/14 22/11/14 Obtain Banks no objection 21 d 12/11/14 22/11/14 Bisue bid documents + tendering	380	Tender Period	45 d	8/7/14		31SF	
Approval 5 d 928/14 10/1/14 Award & Appeal Period 14 d 10/1/14 10/1/14 Mobilization 60 d 10/1/14 10/1/14 He of Second Right 445 d 928/13 1/1/14 Prepation of Expression of Interest 5 d 928/13 1/1/14 Prepation of Expression of Interest 5 d 928/13 1/1/14 Obtain Banks No objection 7 d 928/13 1/1/14 Advertise (local media and International) 21 d 10/1/13 10/1/13 Bidding Period 30 d 10/28/13 1/1/1/13 KenCents Approval 7 d 11/27/13 1/1/1/13 KenCents Approval 7 d 11/27/13 1/1/1/13 Median Banks No objection 21 d 1/1/1/14 1/1/1/14 Obtain Banks No objection 21 d 1/1/1/14 1/1/1/14 Obtain Banks No objection 21 d 1/1/1/14 1/1/1/14 Obtain Banks No objection 21 d 1/1/1/14 2/1/1/14 Bisue bid documents + endering <	381	Evaluation	2 g	9/21/14		32SF	
Award & Appeal Period 14 d 10/1/14 10/15/14 Michilization 445 d 928/13 12/14/14 Hre Obscillation 445 d 928/13 12/14/14 Pre-Qualification 98 d 928/13 12/14/14 Prepain Can Prepain of Expression of Interest 5 d 925/13 10/11/14 Obbain Ranks No objection 7 d 10/7/13 10/7/13 Advertise (local media and International) 21 d 10/7/13 10/2/13 Bidding Period 30 d 10/2/13 11/2/13 11/2/13 Chain Banks No objection 7 d 11/2/13 12/4/13 12/4/13 Medicar Approval 7 d 11/2/13 12/4/13 12/4/13 Peparation of bidding Documents 34 d 11/1/4 12/4/14 12/4/14 Obbain Banks No objection 21 d 11/1/4 12/14/14 Obbain Banks No objection 21 d 11/1/4 12/14/14 Oblain Banks No objection 21 d 11/1/4 12/14/14 Bisue bid documents + lendering 46 d	382	Approval	P 9	9/26/14	10/1/14	33SF	
Mobilization Mobilization 60 d 10/15/14 12/14/14 Pre-Gualification Pre-Gualification 45 d 926/13 12/14/14 Prepair of Expression of Interest 5 d 926/13 1/11/14 Obalin Banks No objection 7 d 9/26/13 1/0/27/13 Advertes (local media and international) 2 d 1/0/27/13 1/0/27/13 Bidding Period Shortist Report Preparation 7 d 1/12/1/3 1/1/27/13 KenCen's Approval 7 d 1/1/27/13 1/1/24/13 1/1/14/14 Obtain Banks No objection 347 d 1/1/14 1/1/14/14 Perparation of bidding Documents 347 d 1/1/14 1/1/14/14 Obtain Banks No objection 2 d 1/1/14 1/1/14 Obtain Banks No objection 2 d 1/1/14 1/1/14 Bissue bid documents 2 d 1/1/14 4/1/14 Bissue bid documents + lendering 45 d 4/1/14 4/1/14 Bissue bid documents + lendering 7 d 4/1/14 4/1/14 Evaluation </th <th>383</th> <th>Award & Appeal Period</th> <th>14 d</th> <th>10/1/14</th> <th></th> <th>4SF</th> <th></th>	383	Award & Appeal Period	14 d	10/1/14		4SF	
Hre of Second Rigg 445 d 9128/13 12/14/14 Pre-Qualification 98 d 928/13 1/1/14 Pepalion of Expression of Interest 5 d 925/13 930/13 Advertee (Local media and International) 21 d 10/7/13 10/7/13 Bedding Period 30 d 10/28/13 11/2/13 Evaluation & Shortist Report Peparation 7 d 11/2/13 12/4/13 KenCen's Approval 7 d 11/2/13 12/11/13 Preparation of bidding Documents 347 d 11/1/14 12/11/13 Preparation of bidding Documents 30 d 11/1/14 1/1/14 Bissue bid documents + lendering 45 d 12/11/14 4/1/14 Bissue bid documents + lendering 45 d 22/14 4/1/14 4/1/14 Bissue bid documents + lendering 45 d 4/1/14 4/1/14 4/1/14 Bissue bid documents + lendering 7 d 4/1/14 4/1/14 4/1/14 Bissue bid documents + lendering 7 d 4/1/14 4/1/14 4/1/14 Bissue bid	384	Mobilization	p 09	10/15/14	12/14/14	I6SF	
Pre-Qualification 98 d 9128/13 1/1/14 Prepation of Expression of Interest 5 d 925/13 1/1/14 Obbin Banks No objection 7 d 107/13 107/13 Bedding Period 30 d 107/13 107/13 Evaluation & Shortist Report Peparation 7 d 11/27/13 12/4/13 KenGen's Approval 7 d 12/4/13 12/4/13 Preparation of bidding Documents 30 d 11/14/14 17/14 Preparation of bidding Documents 30 d 11/14/14 17/14 Obtain Banks no objection 30 d 11/14/14 17/14 Issue bid documents + lendering 30 d 11/14/14 47/14 Issue bid documents + lendering 45 d 17/14 47/14 Evaluation 7 d 41/14/14 47/14 Evaluation 7 d 41/14/14 47/14/14	385	Hre of Second Rig	445 d	9/25/13	12/14/14		
Prepation of Expression of Interest	386	Pre-Qualification	p 86	9/25/13			
Obtain Banks No objection 7 d 9/30/13 10/71/3 Advertise (local media and international) 21 d 10/71/3 10/28/13 Bidding Period 30 d 10/28/13 11/27/13 10/28/13 Evaluation & Shortlist Report Peparation 7 d 11/27/13 12/4/13 Chain Banks No objection 21 d 12/4/13 12/4/14 Preparation of bidding Documents 347 d 11/11/4 13/14/4 Obtain Banks no objection 21 d 1/31/14 13/14/4 Issue bid documents + tendering 25 d 1/31/14 13/1/4 Issue bid documents + tendering 25 d 4/7/4 4/1/14 Evaluation 7 d 4/1/14	387	Prepation of Expression of Interest	2 q	9/25/13		₩SF	
Advertise (local media and international) Bidding Period Evaluation & Shortlist Report Reparation To d 11/27/13 11/27/14 11/27/	388	Obtain Banks No objection	p 2	9/30/13		39SF	
Bidding Period 30 d 1028/13 11/27/13 Evaluation & Shortlist Report Peparation 7 d 11/27/13 12/27/27/27/27/27/27/27/27/27/27/27/27/27	389	Advertise (local media and international)	21 d	10/7/13	10/28/13	JOSF THE	
Evaluation & Shortlist Report Preparation 7 d 11/27/13 12/4/13 12/4/13 12/4/13 12/4/13 12/4/13 12/4/13 12/4/13 12/4/13 12/4/14 12/4/44 12/	390	Bidding Period	P 0E	10/28/13	11/27/13	J1SF	
KenCents Approval 7 d 124/13 12/11/13 Obtain Banks No objection 21 d 12/11/13 1/1/14 4/1/14<	391	Evaluation & Shortlist Report Preparation	p 2	11/27/13	12/4/13	32SF	
Obtain Banks No objection	392	KenGen's Approval	p 2	12/4/13		33SF	
Tendering 347 d 1/1/14 121/414 Preparation of bidding Documents 30 d 1/1/14 1/31/14 1/31/14 1/31/14 1/31/14 2/21/14 1/31/14 2/21/14 4/71/14 In Seve bid documents + tendering 45 d 2/21/14 4/7/	393	Obtain Banks No objection	21 d	12/11/13	1/1/14	95SF	
Preparation of bidding Documents 30 d 1/1/14 1/31/14 1/31/14 1/31/14 2/2	394	Tendering	347 d	1/1/14	12/14/14		
Obbain Banks' no objection 21 d 1/31/14 2/21/14 Issue bid documents + tendering 45 d 2/21/14 4/7/14 Technical Evaluation 35 d 4/7/14 5/12/14 Evaluation 7 d 4/7/14 4/7/14 KenGen Approval 7 d 4/14/14 4/14/14	395	Preparation of bidding Documents	90 g	1/1/14		Jest 1	
Ssue bid documents + tendering 45 d 2/21/14 4/71/14 Technical Evaluation 35 d 4/71/4 5/12/14 Evaluation 7 d 4/71/4 4/4/14 KenGen Approval 7 d 4/14/14 4/4/14	396	Obtain Banks' no objection	21 d	1/31/14		37SF	
Technical Evaluation 35 d 47714 51/21/4 Evaluation 7 d 4/71/4 4/14/14 4/14/14 KenGen Approval 7 d 4/14/14 4/2/114	397	Issue bid documents + tendering	45 d	2/21/14		99SF	
Evaluation 7 d 4/7/14 4/1/4/14 KenGen Approval 7 d 4/1/4/14 4/2/114	398	Technical Evaluation	35 d	4/1/14	5/12/14		
KenGen Approval 7 d 4/14/14	339	Evaluation	p 2	4/7/14	4/14/14	00SF	
	400	KenGen Approval	P Z	4/14/14	4/21/14	11SF	

Planning, Kenya 19 Ngugi

				_	
Obtain Bank's no objection	21 d		5/12/14 40	403SF	
Commercial Evaluation	20 d	5/12/14	7/21/14		
Invite bidders for tender openining	21 d	5/12/14	6/2/14 404SF	404SF	
Evaluation	7 d	6/2/14	6/9/14 405SF	405SF	
KenGen Approval & Appeal	21 d	6/9/14	6/30/14 406SF	406SF	
Obtain Bank's no objection	21 d	6/30/14	7/21/14 408SF	408SF	
Contract Negotaition	26 d	7/21/14	9/15/14		
Invite bidders for Negotiation	21 d	7/21/14	8/11/14 409SF	409SF	
Negotiation & Drafting of contract	7 d	8/11/14	8/18/14 410SF	410SF	
Obtain Bank's no objection	21 d	8/18/14	9/8/14 411SF	411SF	
Signing of contracts	7 d	9/8/14	9/15/14 41	413SF	
Contract Performance	P 06	9/15/14	12/14/14		
Advance Payment	30 d		10/15/14 414SF	414SF	
Mobilization	p 09		12/14/14 415SF	415SF	
Onsite	P0		12/14/14 416SF	416SF	★ 4214
Drilling and Testing	900 q	12/14/14	10/10/15	696	
Custruction Phase	1766 d	8/7/13	6/8/18		
Interfacing with KPLC	31 d	8/7/13	9/7/13		ľ
Contact KPLC	1 d	8/7/13	8/8/13	8/8/13 420SF	•
Obtain counterpart Staff	30 d	8/8/13	9/7/13 423SF	423SF	
Power Plant Construction and Commissioning	1707 d	9/7/13	5/11/18		
Procure Consultants	255 d	9/7/13	5/20/14		
Prepare expression of interest	14 d	9/7/13	9/21/13 424SF	424SF	
Advertise	10 d	9/21/13	10/1/13 425SF	425SF	
Tender period	42 d	10/1/13	11/12/13 426SF	426SF	
Pre-qualify Consultants	14 d	11/12/13	11/26/13 42.7SF	427SF	
Tender Documents	p 09	11/26/13	1/25/14 428SF	428SF	
Tendering Process	42 d	1/25/14	3/8/14	3/8/14 429SF	
Complete Tender Evaluation and Approval (two enve	31 d	3/8/14	4/8/14 430SF	430SF	
Complete Aw ard, Negotion and Contract signing	21 d	4/8/14	4/29/14 431SF	431SF	
Advance Payment and LC	21 d	4/29/14	5/20/14 43	433SF	
Procure Contractor	388 d	5/20/14	6/12/15		
Prepare expression of interest	14 d	5/20/14	6/3/14 434SF	434SF	
Advertise	10 d	6/3/14	6/13/14 435SF	435SF	
Tender period	42 d	6/13/14	7/25/14 436SF	436SF	
Pre-qualify Contractors	20 d	7/25/14	8/14/14 43	437SF	
Tender Documents and Conceptual design	P 09	8/14/14	10/13/14 438SF	438SF	
Tendering Process	P 06	10/13/14	1/11/15 43	439SF	
Complete Tender Evaluation and Approval	P 09	1/11/15	3/12/15 440SF	440SF	
Complete Aw ard, Negotion and Contract signing	30 d	3/12/15	4/11/15 441SF	441SF	
Advance Payment and LC	62 d	4/11/15	6/12/15 451SF	451SF	
Construct Service Power line	270 d	9/15/14	6/12/15		
Make Application	7 d	11/7/14	11/14/14 445SF	445SF	<u> </u>
KPLC quotation Period	P 09	9/15/14	11/14/14 445SF	445SF	
Make payment	30 d	11/14/14	12/14/14 446SF	446SF	

Ngugi 20 Planning, Kenya

